

Attachment E
Project Changes
Contract# EDB-05-22-C103

The following changes are incorporated into this contract. Any further changes after the award will be added below, and signed by both the Project Manager and Contractor. Contractor recognizes that the City has the latitude to make changes as needed.

- 1) Pad design slightly different than depicted in earthwork drawings. Differences include but are not limited to: pad slope +/- 1%, pad size increased, riprap wall instead of concrete block barrier.
- 2) Survey is not required to set tanks, however it is still the contractors responsibility to set tanks according to plan. If tank placement is off to the degree that additional contractors (mechanical and electrical) cannot perform their work then tanks or equipment may require readjustment.
- 3) Placement of generator not as depicted in drawings. New location to be determined.
- 4) Timber Construction to be supplied by contractor. Yellow cedar may be substituted for PT lumber specified in design documents.
- 5) It is necessary that the tanks not be skidded in order to preserve the underside of the skids. The contractor should be confident that the equipment available will be able to transport the tanks without damage. If an occasion occurs where there is damage to the bottom of the skid, then it is at the project manager's discretion whether repairs are necessary and how the situation will be mitigated by the contractor.