

**Contractor Q & A**  
**Contract# EDB-05-18-C102**

- Q1: It is unclear from the contract what supplies for this project are being supplied by the city of Edna Bay. Can you please provide a list?
- A1: Please see the attached Contract Modification PDF and the following list of items to be provided by the City:
- 1: Heavy replacement hinges for the top Gangway transition plate
  - 2: Bolts for the replacement hinges on the top Gangway transition plate
  - 3: Replacement aluminum wear strips for the transition plate to the Float Plane Float
  - 4: UHMW (Ultra High Molecular Weight) wearing edge strip for the Float Plane Float transition plate
  - 5: Heavy duty bearing to replace the blown out bearing on the Gangway roller
  - 6: Two gallons of Kelkote to be applied to all used transition plates on the dock
  - 7: Two pounds of fine texture sand to be mixed into the Kelkote before application to increase grip quality
  - 8: One newly fabricated aluminum transition plate and wear plate from Homestead Skiffs
  - 9: Attachment lag bolts for the newly fabricated transition plate from Homestead Skiffs
- Q2: The contract does not require longshoreman's insurance for work over the water, is this an oversight or is regular comp sufficient?
- A2: It is the responsibility of the Contractor to provide a Proof of Insurance Certificate to the City of Edna Bay. It is also the Contractor's responsibility to make sure any appropriate Class Codes are reported to their Insurance Carrier for the work they are performing.